



**KAMARAJAR PORT LIMITED**  
**(A Mini Ratna Government of India Undertaking)**  
**Vallur (Post), Chennai – 600120.**

**Quotation No.: KPL/OP/ELE/QTN 01/2017**

**Quotation for “Shifting of Under Ground (UG) Cables and Dismantling of**  
**Street Light Poles at Kamarajar Port”**

**Due date of Submission: 1500 Hrs on 22/06/2017**

**Date & Time of Opening: 1530 Hrs on 22/06/2017**

**KAMARAJAR PORT LIMITED****Quotation for the work of “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”****Information to the bidders**

<i>Sl.No</i>	<i>Details</i>	<i>Description</i>
1	Name of work	Quotation for <b>“Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”</b> at an estimated cost of Rs. 1,68,300/-
2	Last date of submission of quotation	On or before 15 00 hrs on 22.06.2017
3	Place of Submission and Opening	THE DEPUTY GENERAL MANAGER ( C ) KAMARAJAR PORT LIMITED, Vallur (post), Chennai-120.
4	Date of opening	22.06.2017 at 15 30 hrs
5	Earnest Money Deposit	Rs.3,400/-

**Quotation for the work of “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”**

**QUOTATION NO. : KPL/OP/ ELE/QTN01/2017**

**General**

Quotation for the work of “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”.

**Validity**

The quotation shall be valid for a period of 120 Days from the last date for submission of the quotation.

**1.3 EARNEST MONEY DEPOSIT (EMD)**

The Quotation should be accompanied by Earnest Money Deposit of **Rs. 3,400** /- in the form of Demand Draft drawn in favor of **Kamarajar Port Limited** on any Indian Nationalized Bank enforceable and encashable at Chennai and enclose the same along with the Quotation.

Any quotation received without EMD will be summarily rejected. The EMD of the unsuccessful Bidders will be refunded after the issuing of work order to the successful bidder and the EMD of the successful Bidder will be refunded after submission of security deposit by the successful bidder. No interest will be allowed on the EMD amount from the date of its receipt until its refund. The EMD will be released on suo motto basis without any application from tenderers.

The firms registered with **NSIC/MSME registered Contractor /Suppliers are exempted from payment of EMD.**

**Submission of quotation.**

The quotation shall be submitted in a sealed cover and addressed to **The Deputy General Manager (C), Kamarajar Port Limited, Vallur (Post), Chennai-600 120** indicating the name of work on or before 22/06/2017 at **15 00 hours** as per the following.

1. Schedule “A” consists of Scope of work, Detailed Technical Specifications, Instruction to Bidders and Payment Terms etc.
2. Bill of Quantities (Schedule of quantities) as per schedule “B”.
3. Schedule “C” consists of General Conditions.

**OPENING DATE**

The quotation will be opened on **22/06/2017 at 1530 hours at the above address.**

**Clarification / Information**

Any clarification / Information can be obtained from Assistant Manager (Electrical) at the Port Office / Ph: No. 044-27950030, extn.: 336

**Deputy General Manager (C)**

**Quotation for the work of “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”**

**Schedule ‘A’**

**Scope of work:**

The scope of work covered in this tender includes “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port” as per the specifications and as directed at site.

**Detailed specification:**

**Retriving of UG cable:**

Removing of existing 3 core, 300Sq.mm HTUG cable, 31/2 core, 300Sq.mm LTUG cable, 31/2 core, 70Sq.mm LTUG cable and 4 core 25Sq.mm LTUG cable along with Cable troughs and Bricks including materials if any by excavation of earth not more than 1.5 Mtr. depth and Removal of cover slab from the existing RCC cable trench. If any damage occurs during retring, the same to be rectified by the contractor at their cost. Refilling the excavation and stacking the cover slabs within a lead of 1KM as directed at site.

**Re-Routing of UG cable:**

The work includes excavation of earth not more than 1.5 Mtr. depth, re-laying of removed 3 core, 300Sq.mm HTUG cable, 31/2 core, 300Sq.mm LTUG cable , 31/2 core, 70Sq.mm LTUG cable and 4 core 25Sq.mm LTUG cable and protecting the cable with troughs and Bricks. If any damage occurs during relaying, the same to be rectified by the contractor at their cost. The same trench to be refilled after laying of cable.

**Dismantling of 11Mtr. RCC / MS pole:**

The 11Mtr. RCC pole along with light fittings shall be dismantled from the foundation, remove the PCC concrete and return the MS Skeleton rod and light fittings without damage to the KPL store within a lead of 1KM as directed at site. If any damage occurs to the light fittings during dismantling, the same to be rectified by the contractor at their cost. The 11Mtr. MS pole along with light fittings shall be dismantled from the foundation and return the same to KPL store without damage. If any damage occurs to the light fittings / pole during dismantling, the same to be rectified by the contractor at their cost.

**3 ½ core, 300Sq.mm LTUG cable Straight through Joint Kit:**

The straight through joint kit shall be heat shrinkable and suitable for 3 ½ core, 300Sq.mm LTUG cable as per latest IS.

**Bricks:**

The bricks shall be kiln burnt and standard size as per latest IS.

**Dismantling and Re-installation of Electrical Outdoor Panel Board:**

The 400Amps outdoor panel board shall be removed from the existing foundation, the same to be shifted to the new location as directed at site, construction of suitable pedestal using bricks on both sides including civil works, supply and installation of foundation bolt and nuts and reinstallation of the above panel on the newly constructed pedestal. If any damage occurs during removal and reinstallation, the same to be rectified by the contractor at their cost.

Any other works required for proper completion of work shall be done by the contractor at their cost.

**It is the responsibility of the contractor to inspect the site before submission of quotation documents to know the full implication of the contract.**

**Instruction to the Bidders:**

- Bidder shall quote his rated for each item for work in schedule of the quantity both in figures and in words and also fill up the amount column without any omission.
- The completed quotation shall be submitted a sealed envelope super-scribed as “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”.
- The sealed cover should be addressed to “**The Deputy General Manager (C) Kamarajar Port Limited, Vallur Post, Chennai-600 120**”. All communications to be addressed to the above address only.
- **The entire work shall be completed within 30days from the date of issue of the order.**
- The contractor shall deposit **10 %** of the contract value as Security deposit for the due fulfillment of the conditions of the contract, immediately after receipt of the order in the form of Demand Draft.

The Security Deposit shall not bear any interest. The Security Deposit shall be forfeited if the contractor has failed to fulfill any of the conditions of the above contract. The Security Deposit shall be refunded to the contractor after satisfactory completion of the contract period and after payment of final bill.

- The contractor shall submit entire set of quotation duly signed and stamped on all the pages of the documents (in token of acceptance of all the conditions stipulated therein).
- Your quoted price shall be inclusive of all taxes duties, levies etc except service tax.
- **Liquidated Damages**  
In case of delay in completion of the supply, liquid damages (L.D) may be levied at the rate of ½ % of the contract value per week of delay or part thereof, subject to a maximum of 10 % of the contract price.

**Payment Terms**

- 100% payment will be made after completion and acceptance of the work on submission of the bill.

**KAMARAJAR PORT LIMITED****Quotation for the work of “Shifting of Under Ground (UG) Cables and Dismantling of Street Light Poles at Kamarajar Port”**  
**Bill of Quantities (Schedule of quantities)****SCHEDULE 'B'**

<b>Sl.No</b>	<b>Description</b>	<b>QTY</b>	<b>UNIT</b>	<b>UNIT Rate in Rs.</b>	<b>Total Amount in Rs.</b>
<b>(1)</b>	<b>(2)</b>	<b>(3)</b>	<b>(4)</b>	<b>(5)</b>	<b>(3)*(5)</b>
1	Labour charges for retring and re-routing of 3core, 300Sq.mm HTUG cable and 31/2 core, 300Sq.mm LTUG cable, 31/2 core, 70Sq.mm LTUG cable and 4 core 25Sq.mm LTUG cable and protecting the cable with bricks / cable troughs including earth work excavation to a depth not more than 1.5Mtr and removing the cover slabs including cost of all material, labour, transport, fuel etc as per technical specifications and as directed at site.	500	Rmtr		
2	Supply of kiln burnt bricks including cost of all material, labour, transport, fuel etc as per technical specifications and as directed at site	3600	No.		
3	Dismantling of 11Mtr. MS / RCC pole along with light fitting and return the same to KPL store including materials, labours, shifting, transportation etc as per technical specifications and as directed at site	10	No.		



4	Dismantling and re-installation of electrical power panel including construction of pedestal, cost of all material, labour, transport, fuel etc as per technical specifications and as directed at site	1	LS		
5	Supply of 3 1/2 core, 300Sq.mm LTUG cable straight through joint kit including cost of all material, labour, transport, fuel etc as per technical specifications and as directed at site.	4	No.		
6	Labour charges for providing 3 1/2 core, 300Sq.mm LTUG cable straight through joint kit including cost of all material, labour, transport, fuel etc as per technical specifications and as directed at site.	4	No.		
<b>Total amount in Rs.</b>					

**Total Amount in Words:**

(Rupees .....  
..... Only)

**Signature of the contractor with seal**

**KAMARAJAR PORT LIMITED****SCHEDULE – “C”**  
**GENERAL CONDITIONS**

1. The quantities given in the schedule of quantities are those upon which the approximate estimated cost of the work is based but they are subject to alterations, omissions, deductions and additions and do not necessarily show the actual quantities of the work to be done.
2. The work shall be done to the satisfaction of the Engineer in charge or his representative. The works shall be done in accordance with the specifications laid down in the relevant standards set up by the Indian Standard. Any item of work carried out not in accordance with the specifications and other conditions will be rejected irrespective of the apparent quality of the work.
3. The work is to be carried out with due diligence and executed to a workman like manner. The material used when supplied by the contractor is to be of the best of its kind and in all cases to be subject to the approval of the Engineer in charge whose decision to the rate of progress the quality of the work or materials, sizes etc., is final.
4. The Engineer in charge may cancel the contract at his opinion at any time without notice for any reason including poor progress of work and may remove bad work or materials and have it replaced deducting the value of the work rejected or material removed of the cost of replacing it as he may think proper from any amount due or that may become due to the contractor. The decision of the Engineer in charge is final and will be binding on the contractor.
5. In case the contractor leaves work incomplete the Engineer in charge shall have the right to have the work completed through any other agency and recover the extra expenditure incurred by the KPL in so doing from any money due or to become due to the contractor.
6. The contractor shall conform to and comply with the regulations and by laws of the Kamarajar Port Limited of all other local authorities such as the Corporation of Chennai. The Chief Electrical Inspector to the Government of Tamilnadu, the Tamilnadu Electrical system, the Factories Act., the Government Customs and Police Department, etc., The Contractor shall conform to rules, regulations etc., concerning injury to workmen compensation for injury to workmen, insurance for workmen etc., The contractor shall also conform to contract labour (Regulations and Abolition) Central Rule 1971 etc.,
7. The contractor shall be responsible for any accident, damage or injury caused to any of his employees or property or any person or property in course of the work and shall hold the KPL blameless in respect thereof and also in respect of any claim made by any person or any reasons whatsoever.

8. The contractor shall be solely responsible for reporting to the KPL and Police Department immediately of any serious or fatal accident inside the Kamarajar Port premises to any of his employees / workmen engaged by him or any person involved in an accident as a whole of the work.
9. The work shall be carried out without causing any inconvenience to the KPL and to other works in progress in the neighborhood and any losses of the KPL.
10. Admission into the harbour is regulated by passes for contractor and his staff and workers. The contractor shall obtain necessary passes for his men and himself paying the charges as fixed from time to time. At the completion of the work the contractor shall return all passes issued. Failure to return any pass will entail a penalty of Rs.50/- (Rupees fifty only) per pass as the case may be plus surcharge as may be levied by the KPL from time to time.
11. Only vehicles licensed by the KPL will be allowed to play inside the harbour.
12. The work shall be carried out only during KPL's working days between 9.45 A.M. and 4.45 P.M.
13. The quantities of work executed will be measured and payment made once a month generally except in the case of work for which the time for completion is specified as six weeks or less than six week in which case payment will be made only on satisfactory completion of the work. The bill for the work shall be prepared and submitted by the contractor in the KPL's prescribed form.
14. It shall be clearly understood that the rates mentioned in the schedules are inclusive of everything required to be done for the proper completion of the work according to the specifications drawings, general conditions and special conditions even though specific mention thereof has been omitted in the specification and drawings.
15. The contractor should be Measurements for the work done in KPL's prescribed format. The measurements submitted by the contractor will be verified by the person authorized by the Engineer in charge and the contractor will be given the opportunity for witnessing the verification.
16. All payments made by KPL to the contractor for the work shall be rounded of the nearest rupee.

**DGM (C)**  
**Kamarajar Port Limited.**